

LEGEND

- TOPSOIL AND SEED A AS SPECIFIED MINIMUM 150mm TOPSOIL DEPTH
- TOPSOIL AND SEED B AS SPECIFIED MINIMUM 150mm TOPSOIL DEPTH
- EXISTING DECIDUOUS TREE TO REMAIN
- EXISTING CONIFEROUS TREE TO REMAIN
- PROPOSED DECIDUOUS SHADE TREE
- PROPOSED CONIFEROUS TREE
- PROPOSED DECIDUOUS SHRUBS
- PROPOSED ORNAMENTAL GRASSES
- PROPOSED PERENNIALS
- 2.4m WOOD PRIVACY FENCE
- 2.4m SCREENED CHAIN LINK FENCE
- 2.4m CHAIN LINK FENCE
- 1.8m CHAIN LINK FENCE
- Xx / 0 — PLANT SPECIES / QUANTITY
- XX / D-1 — DETAIL NUMBER / SHEET NUMBER

LANDSCAPE NOTES:

1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH BY-LAWS AND CODES HAVING JURISDICTION OVER SITE LOCATION.
2. COMPLETE ALL WORK TO THE SATISFACTION OF THE LANDSCAPE ARCHITECT.
3. REPORT ANY CHANGES, DISCREPANCIES OR SUBSTITUTIONS TO THE LANDSCAPE ARCHITECT FOR REVIEW. OBTAIN APPROVAL FROM THE LANDSCAPE ARCHITECT BEFORE PROCEEDING.
4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE EXISTING SERVICE LOCATIONS.
5. EXACT LOCATIONS OF PLANT MATERIAL WILL BE DETERMINED BY PLACEMENT OF SITE SERVICES SUCH AS HYDRO VAULTS, METERS, UTILITIES ROOF RAIN WATER LEADERS, DRIVEWAYS, LIGHT STANDARDS, ETC.
6. SUPPLY ALL PLANT MATERIAL IN ACCORDANCE WITH THE CANADIAN STANDARDS FOR NURSERY STOCK (9th Ed.).
7. INSTALL PLANT MATERIAL ACCORDING TO DETAILS SHOWN.
8. DISTURBED SOIL AREAS AROUND TREES AND SHRUBS ARE TO BE COVERED WITH SHREDDED CONIFER BARK MULCH SUCH AS 'CANADA RED' OR 'GRO-BARK' SPM MULCH, OR APPROVED EQUIVALENT. ALTERNATIVE MULCHES MUST BE APPROVED BY THE LANDSCAPE ARCHITECT.
9. CONTRACTOR TO UTILIZE LAYOUT DIMENSIONS WHERE PROVIDED.
10. PROVIDE PLANTING BED AREA AS NOTED ON THE DRAWING OR TO ACCOMMODATE MATURE SIZE OF PLANT MATERIAL.
11. ALL SUPPORT SYSTEMS MUST BE REMOVED BY THE CONTRACTOR AT TIME OF FINAL ACCEPTANCE. NO EXTRAS WILL BE PAID TO COMPLETE THIS WORK.
12. SUPPLY AND PLACE TOPSOIL IN ACCORDANCE WITH OPSS 802 TO A MINIMUM DEPTH OF 150mm UNLESS OTHERWISE SPECIFIED.
13. SUPPLY AND PLACE SOD IN ACCORDANCE WITH OPSS 803 UNLESS OTHERWISE SPECIFIED.
14. SUPPLY AND PLACE SEED IN ACCORDANCE WITH OPSS 804 UNLESS OTHERWISE SPECIFIED. ALL 5:1 OR GREATER SLOPES TO BE SEEDED WITH TACIFIER. CONTRACTOR TO PROVIDE NECESSARY EROSION CONTROL PROTECTION AS REQUIRED TO ENSURE SOIL STABILIZATION AND PROPER SEED GERMINATION.
15. ALL DIMENSIONS IN METRES UNLESS OTHERWISE NOTED.
16. IF DISCREPANCIES ARISE BETWEEN PLANT MATERIAL COUNT SHOWN ON DRAWING AND PLANT LIST, THE DRAWING SHALL BE CONSIDERED CORRECT.
17. CONTRACTOR TO PROVIDE MINIMUM TWO (2) YEAR WARRANTY FROM DATE ACCEPTED ON ALL WORK UNLESS OTHERWISE SPECIFIED.
18. ANY SITE PLAN OR GRADING AND SERVICING SHOWN IS FOR INFORMATION ONLY. REFER TO APPROVED DRAWINGS.
19. NOT FOR CONSTRUCTION UNLESS STAMPED, SIGNED AND DATED BY LANDSCAPE ARCHITECT.
20. DRAWINGS NOT TO BE REPRODUCED WITHOUT WRITTEN CONSENT FROM LANDSCAPE ARCHITECT.
21. APPROVAL OF LANDSCAPE PLAN TO BE OBTAINED FROM MUNICIPALITY.
22. FOR GRADING AND SERVICING INFORMATION REFER TO THE ENGINEER'S DRAWINGS.
23. FOR LIGHTING INFORMATION AND POWER DISTRIBUTION REFER TO THE ELECTRICAL DRAWINGS.

SEED MIX A:

CONTRACTOR TO SOW NURSE CROP AVENA SATIVA OVER ENTIRE AREA; TO BE SEEDED AT A RATE OF 25kg/ HECTARE.

8145 - RURAL ONTARIO ROADSIDE MIXTURE BY OSC SEEDS (519.886.0557). TO BE SEEDED AT A RATE OF 25KG PER HA. SEED MIX TO INCLUDE:

Black Eyed Susan (Rudbeckia hirta)	2%
Blue Vervain (Verbena hastata)	2%
Bonset (Eupatorium perfoliatum)	1%
Canada Wild Rye (Elymus canadensis)	24%
Dense Blazing Star (Liatris spicata)	1%
Foxglove/Beard Tongue (Penstemon digitalis)	2%
Indian grass (Sorghastrum nutans)	20%
Little Blue Stem (Schizachyrium scoparium)	20%
New England Aster (Aster novae-anglais)	2%
Showy Tick Trefoil (Desmodium canadense)	3%
Virginia Wild Rye (Elymus virgatum)	22%
Wild Bergamot (Monarda fistulosa)	1%

SEED MIX B:

CONTRACTOR TO SOW NURSE CROP AVENA SATIVA OVER ENTIRE AREA; TO BE SEEDED AT A RATE OF 25kg/ HECTARE.

8245 SWM POND MIX WET/DRY MIX BY OSC SEEDS (519.886.0557). TO BE SEEDED AT A RATE OF 25KG PER HA. SEED MIX TO INCLUDE:

Black Eyed Susan (Rudbeckia hirta)	3%
Canada Wild Rye (Elymus canadensis)	20%
Fox Sedge (Carex vulpinoidea)	17%
Indiangrass (Sorghastrum nutans)	15%
New England Aster (Aster novae-anglais)	3%
Spotted Joe Pye Weed (Eupatorium maculatum)	1%
Switchgrass (Panicum virgatum)	20%
Virginia Wild Rye (Elymus virgatum)	20%
Wild Bergamot (Monarda fistulosa)	1%

PROPOSED PLANTING SCHEDULE

KEY	BOTANICAL NAME	COMMON NAME	CAL.		COND	MATURE HEIGHT (m)	MATURE SPREAD (m)	O.C. SPACING (m)	QNTY.	%
	DECIDUOUS TREES									
AF	Acer x Fremanii 'Autumn Blaze'	Freeman Maple	60mm		W.B.	18.0m	12.0m	10.0m	5	11.9%
CC	Cercis canadensis 'Hearts of Gold'	Hearts of Gold Redbud	60mm		W.B.	3.6m	6.0m	6.0m	8	19.0%
CR	Cornus racemosa	Gray Dogwood		150cm	W.B.	4.0m	4.0m	4.0m	8	19.0%
FS	Fagus sylvatica	European Beech	60mm		W.B.	18.0m	15.0m	10.0m	6	14.2%
GB	Ginkgo biloba 'Autumn Gold'	Maidenhair Tree	60mm		W.B.	15.0m	9.0m	10.0m	4	9.6%
LT	Liriodendron tulipifera 'Fatigiata'	Columnar Tulip Tree	60mm		W.B.	16.0m	6.0m	6.0m	4	9.6%
TC	Tilia cordata	Littleleaf Linden	60mm		W.B.	21.0m	15.0m	10.0m	7	16.7%
								TOTAL	42	100%
	CONIFEROUS TREES									
TO	Thuja occidentalis	Northern White Cedar		200cm	W.B.	12.0m	4.5m	6.0m	14	
								TOTAL	14	
	SHRUBS									
Cs	Cornus sanguinea 'Midwinter Fire'	Bloodtwig Dogwood			#2 cont.	1.8m	1.8m	1.8m	90	
Fo	Forsythia ovata	Korean Forsythia			#2 cont.	1.5m	2.1m	2.1m	45	
Vr	Viburnum x rhytidophylloides 'Red Balloon'	Lantanaphyllum Viburnum			#2 cont.	2.4m	2.4m	3.0m	51	
								TOTAL	186	
	PERENNIALS/ORNAMENTAL GRASSES									
ca	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass			#1 cont.	1.8m	0.6m	0.6m	246	
pa	Pennisetum alopecuroides 'Desert Plains'	Desert Plain Fountain Grass			#1 cont.	1.2m	1.2m	1.2m	114	
sh	Sedum 'Herbsfreude'	Autumn Joy Stonecrop			#1 cont.	0.6m	0.6m	0.6m	253	
								TOTAL	613	

True North — Project North

10 5 0 10 20 30

1:750 (m)

CLIENT

AMERICAN IRON AND METAL

9100 BOUL HENRI-BOURASSA E, MONTREAL-EST, QC

COPYRIGHT

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by IBI Group is forbidden. Do not scale drawings. Use only dimensioned drawings. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general conformance before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies

ISSUES

No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2022-03-25
2	REISSUED FOR SPA	2022-12-20
3	ISSUED FOR TENDER	2023-02-06

KEY PLAN



CONSULTANTS

NOT FOR CONSTRUCTION

SEAL

PRIME CONSULTANT

IBI GROUP
Suite 200 - 360 James Street North
Hamilton ON L8L 1H5 Canada
tel 905 546 1010 fax 905 546 1011
ibigroup.com

PROJECT

McADOOS LANE

1533 McADOOS LANE, KINGSTON, ON

PROJECT NO: 124600	
DRAWN BY: **T. KEMP**	CHECKED BY: **T. O'BRIEN**
PROJECT MGR: **T. TUCKER**	APPROVED BY: **T. O'BRIEN**

SHEET TITLE

LANDSCAPE PLAN

SHEET NUMBER	ISSUE
L-1	1

SCALE CHECK 10mm 1 in

File Location: T:\124600_1533McAdoo\LN\7.0_Production\7.03_Design\05_Landscape\Sheets\124600LP.dwg Last Saved: February 6, 2023, by taylor.kemp Plotted: Monday, February 6, 2023 2:42:58 PM by Taylor Kemp



NOTES:

- OBTAIN WRITTEN CONFIRMATION OF UTILITY LOCATES PRIOR TO COMMENCEMENT OF DIGGING
- DIG ALL HOLES BY HAND WHEN CLOSER THAN 1.0M TO UNDERGROUND POWER, TELEPHONE AND GAS ALIGNMENTS
  - USE ROOT DEFLECTOR ON THE UTILITY SIDE OF REQUIRED
  - ENSURE BASE OF TREE PIT IS STABLE IN ORDER TO MAINTAIN THE DESIRED TREE LEVEL AND GRADE
  - TREES TO BE SPRAYED WITH APPROVED ANTI-DESSICANT PRIOR TO TRANSPLANTING UNLESS PLANTED WITHIN 48 HOURS OF DIGGING (IF PLANTED IN FULL LEAF)
- SET TREE 50mm HIGHER THAN SURROUNDING GRADE TO ALLOW FOR SETTLEMENT
- - SCARIFY COMPACTED SUBGRADE TO 500MM DEEP IN AREA 5 X ROOTBALL DIAMETER
  - DIG PIT 300MM WIDER THAN ROOTBALL PERIMETER
  - MULCH WITH SHREDDED BARK OR COMPOSTED HARDWOOD CHIPS
  - TRUNK PROTECTION
    - MECHANICAL INJURY : USE PLASTIC TREE COLLAR
    - ANIMAL INJURY : USE SPIRAL TREE GUARDS OR SCREEN COLLARS
    - SUNSCALD INJURY : PAINT TRUNK WITH WHITE LATEX OR WHITE-WASH, OR WRAP WITH BURLAP, KRAFT WRAP INSTALLED FROM THE GROUND UP TO ABOVE LOWEST BRANCHES
    - LAWN MOWER INJURY : USE SPLIT CORRUGATED BRAIN COLLARS
  - REMOVE TREE STAKES AND TREE WRAP AFTER ONE SEASON

1 / D-1 BALLED & BURLAPPED/WIRE BASKET DECIDUOUS TREE
N.T.S.



NOTES:

- OBTAIN WRITTEN CONFIRMATION OF UTILITY LOCATED PRIOR TO COMMENCEMENT OF DIGGING
- DIG ALL HOLES BY HAND WHEN CLOSER THAN 1000mm TO UNDERGROUND POWER, TELEPHONE AND GAS ALIGNMENT
- USE ROOT DEFLECTOR ON THE UTILITY SIDE IF REQUIRED.
- ENSURE BASE OF TREE PIT IS STABLE IN ORDER TO MAINTAIN THE DESIRED TREE LEVEL AND GRADE.
- ENSURE BASE OF TREE PIT IS STABLE IN ORDER TO MAINTAIN THE DESIRED TREE LEVEL AND GRADE
- TREES TO BE SPRAYED WITH APPROVED ANTI-DESSICANT PRIOR TO TRANSPLANTING UNLESS PLANTED WITHIN 47 HOURS OF DIGGING (IF PLANTED IN FULL LEAF)
- SET TREE 500mm HIGHER THAN SURROUNDING GRADE TO ALLOW FOR SETTLEMENT.
- SCARIFY COMPACTED SUB-GRADE TO 500mm DEEP IN AREA 5x ROOTBALL DIAMETER.
- DIG PIT 300mm WIDER THAN ROOTBALL PERIMETER
- MULCH WITH SHREDDED BACK OR COMPOSTED HARDWOOD CHIPS
- REMOVE TREE STAKES AND TREE WRAPS AFTER ONE SEASON

TRUNK PROTECTION:

- MECHANICAL INJURY: USE PLASTIC TREE COLLAR
- ANIMAL INJURY: USE SPIRAL TREE GUARDS OR SCREEN COLLARS
- SUNSCALED INJURY: PAINT TRUNK WITH WHITE LATEX OR WHITE-WASH, OR WRAP WITH BURLAP, KRAFT WRAP INSTALLED FROM THE GROUND UP TO ABOVE THE LOWEST BRANCHES
- LAWN MOWER INJURY: USE SPLIT CORRUGATED BRAIN COLLARS

3 / D-1 BALLED & BURLAPPED/WIRE BASKET DECIDUOUS TREE ON SLOPE
N.T.S.



NOTES:

1. SOIL MIXTURE: FOUR (4) PARTS NATIVE SOIL, ONE (1) PART WELL ROTTED COMPOST.
2. SAUCER SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING PLANTING.
3. ALL DIMENSIONS ARE IN mm.
4. IN POORLY DRAINED SOILS PLANT SHRUB SLIGHTLY HIGHER THAN ADJACENT GRADE.
5. ALL PLANTS TO BE STRAIGHT AND PLANTED VERTICALLY REGARDLESS OF SLOPE.

5 / D-1 BALLED AND BURLAPPED/POTTED SHRUB
N.T.S.



NOTES:

1. SOIL MIXTURE: FOUR (4) PARTS NATIVE SOIL, ONE (1) PART WELL ROTTED COMPOST.
2. SAUCER SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING PLANTING.
3. ALL DIMENSIONS ARE IN mm.
4. CUT AND REMOVE CONTAINER. SCARIFY ROOTBALL SIDES.
5. ALL PLANTS TO BE STRAIGHT AND PLANTED VERTICALLY REGARDLESS OF SLOPE.

CONTRACTOR SHALL PROVIDE 75mm MULCH FOR ALL PERENNIALS EXCEPT GROUNDCOVERS UNLESS SPECIFIED OTHERWISE.

6 / D-1 CONTAINER GROWN PERENNIAL/GRASS
N.T.S.



CONTRACTOR SHALL PROVIDE BURLAP WRAP FOR WINTER PROTECTION FOR DURATION OF MAINTENANCE AND WARRANTY PERIOD.



NOTES:

1. SOIL MIXTURE: FOUR (4) PARTS NATIVE SOIL, ONE (1) PART WELL ROTTED COMPOST.
2. SAUCER SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING PLANTING.
3. ALL DIMENSIONS ARE IN mm.
4. STAKING SCHEDULE:
   - < 2500mm HT. - ONE STAKE
   - > 2500mm HT. - TWO STAKES
   - SPADED TREES - THREE STAKES OR GUY WIRES
   - ALL SUPPORT SYSTEMS MUST BE REMOVED ONCE TREE IS ESTABLISHED.
5. ALL TREES TO BE STRAIGHT AND PLANTED VERTICALLY REGARDLESS OF SLOPE.
6. TOP OF ROOT FLARE SHALL BE POSITIONED 50mm ABOVE GRADE.

2 / D-1 BALLED & BURLAPPED/WIRE BASKET CONIFEROUS TREE
N.T.S.



NOTES:

- OBTAIN WRITTEN CONFIRMATION OF UTILITY LOCATED PRIOR TO COMMENCEMENT OF DIGGING
- DIG ALL HOLES BY HAND WHEN CLOSER THAN 1000mm TO UNDERGROUND POWER, TELEPHONE AND GAS ALIGNMENT.
- USE ROOT DEFLECTOR ON THE UTILITY SIDE IF REQUIRED.
- ENSURE BASE OF TREE PIT IS STABLE IN ORDER TO MAINTAIN THE DESIRED TREE LEVEL AND GRADE.
- ENSURE BASE OF TREE PIT IS STABLE IN ORDER TO MAINTAIN THE DESIRED TREE LEVEL AND GRADE
- TREES TO BE SPRAYED WITH APPROVED ANTI-DESSICANT PRIOR TO TRANSPLANTING UNLESS PLANTED WITHIN 47 HOURS OF DIGGING (IF PLANTED IN FULL LEAF)
- SET TREE 500mm HIGHER THAN SURROUNDING GRADE TO ALLOW FOR SETTLEMENT.
- SCARIFY COMPACTED SUB-GRADE TO 500mm DEEP IN AREA 5x ROOTBALL DIAMETER.
- DIG PIT 300mm WIDER THAN ROOTBALL PERIMETER
- MULCH WITH SHREDDED BACK OR COMPOSTED HARDWOOD CHIPS
- REMOVE TREE STAKES AND TREE WRAPS AFTER ONE SEASON

TRUNK PROTECTION:

- MECHANICAL INJURY: USE PLASTIC TREE COLLAR
- ANIMAL INJURY: USE SPIRAL TREE GUARDS OR SCREEN COLLARS
- SUNSCALED INJURY: PAINT TRUNK WITH WHITE LATEX OR WHITE-WASH, OR WRAP WITH BURLAP, KRAFT WRAP INSTALLED FROM THE GROUND UP TO ABOVE THE LOWEST BRANCHES
- LAWN MOWER INJURY: USE SPLIT CORRUGATED BRAIN COLLARS

4 / D-1 BALLED & BURLAPPED/WIRE BASKET CONIFEROUS TREE ON SLOPE
N.T.S.



7 / D-1 CONCRETE PAVING
N.T.S.

CLIENT

AMERICAN IRON AND METAL

9100 BOUL HENRI-BOURASSA E, MONTREAL-EST, QC

COPYRIGHT

This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by IBI Group is forbidden. Do not scale drawings. Report discrepancies immediately to IBI Group. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general conformance before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies

ISSUES

No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2022-03-25
2	REISSUED FOR SPA	2022-12-20
3	ISSUED FOR TENDER	2023-02-06

KEY PLAN



CONSULTANTS

NOT FOR CONSTRUCTION

SEAL

PRIME CONSULTANT

IBI

IBI GROUP
Suite 200 - 360 James Street North
Hamilton ON L8L 1H5 Canada
tel 905 546 1010 fax 905 546 1011
ibigroup.com

PROJECT

McADOOS LANE

1533 McADOOS LANE, KINGSTON, ON

PROJECT NO: 124600	
DRAWN BY: **T. KEMP**	CHECKED BY: **T. O'BRIEN**
PROJECT MGR: **T. TUCKER**	APPROVED BY: **T. O'BRIEN**

SHEET TITLE

LANDSCAPE DETAILS

SHEET NUMBER	ISSUE
D-1	1

SCALE CHECK 1 in 10mm

File Location: T:\124600_1533McAdoo_N7.0_Production\7.03_Design\05_Landscape\Sheets\124600LP.dwg Last Saved: February 6, 2023, by taylor.kemp Plotted: Monday, February 6, 2023 2:42:35 PM by Taylor Kemp



ELEVATION

SECTION A

NOTES
1. ALL MATERIALS, COMPONENTS AND WORKMANSHIP TO CONFORM TO BUILDING AND LOCAL BY-LAWS.
2. FENCES CONSTRUCTED ON BERMS:
   A) EXTEND FOOTINGS 1500MM INTO UNDISTURBED SUB-GRADE.
   B) ERECT FENCE ALONG CENTRE-LINE OF BERM.
3. ALL WOOD TO BE PRESSURE TREATED SELECTED MAINLY FOR GOOD APPEARANCE ALL MEMBERS SHALL BE FREE OF WANE AND BARK POCKETS. ALL TORN GRAIN SHALL BE ELIMINATED BY SANDING AND PLANNING. MEMBERS EXHIBITING MODERATE TO HEAVY KNOTS SHALL BE WELL DISTRIBUTED THROUGHOUT THE SITE.
4. ALL WOOD TO BEAR LUMBER GRADING STAMP.
5. FASTENERS SHALL HAVE EXTERIOR GRADE FINISHES.
6. ALL GALVANIZING TO BE HOT DIPPED IN CONFORMANCE TO CSA STANDARD C164.
7. DRIVE ALL FASTENER HEADS BELOW SURFACE OF WOOD. USE SUFFICIENT SIZE AND QUANTITY OF FASTENERS TO ENSURE A STABLE, SECURE STRUCTURE.
8. STEP FENCE PANELS MINIMUM OF 100 - 200mm AT POSTS AS REQUIRED BY GRADE CONDITIONS. SLOPING OF PANELS MAY BE REQUIRED FOR CERTAIN GRADE CONDITIONS - CONSULTANT'S APPROVAL REQUIRED.
9. ALL LUMBER SIZES ARE ACTUAL SIZES RATHER THAN NOMINAL SIZES.
10. CONCRETE TO HAVE MINIMUM COMPRESSIVE STRENGTH OF 20 MPA @ 20 DAYS WITH 5-7% AIR ENTERTAINMENT.
11. SEE LANDSCAPE PLAN FOR FENCE LOCATION.
12. ENSURE NO GAPS BETWEEN VERTICAL FENCE BOARDS.

GENERAL LAYOUT NOTES:

1. ALL FENCES ADJACENT TO ROAD ALLOWANCES AND WALKWAYS TO BE ERECTED 0.15M ONTO PRIVATE PROPERTY. FENCING IS NOT TO BE ERECTED ON THE LOT LINE OR INTO ANY ROAD ALLOWANCE OR EASEMENT.

2. FOOTING AND EXCAVATION TO BE ENTIRELY ON PRIVATE PROPERTY.

1 / D-2 2.4m WOOD PRIVACY FENCE AND DOUBLE SWING GATE
N.T.S.



NOTES:
1. CONTRACTOR TO VERIFY DIMENSIONS ON SITE AND PROVIDE SHOP DRAWINGS FOR APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO FABRICATION
2. ALL POSTS AND RAILS SHALL BE SCHEDULE 40 GALVANIZED STEEL PIPE, ELECTROSTATICALLY PAINTED BLACK, AND CONFORMING TO CURRENT SPECIFICATIONS FOR BLACK AND HOT DIPPED ZINC COATED (GALVANIZED) WELDED AND SEAMLESS PIPE FOR ORDINARY USES.
3. ALL HARDWARE TO BE GALVANIZED.
4. ALL FENCE COMPONENTS TO BE OF A SUITABLE ALUMINUM ALLOY OR OF A STEEL DUCTILE IRON, ALSO PAINTED BLACK.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.
6. LINE POSTS SHALL BE SET AT 3.0m CENTRES
7. BOTTOM RAIL AND FINISHED GRADE 38-75mm CLEARANCE MAX.

2 / D-2 CHAIN LINK FENCE & DOUBLE SWING GATE (HEIGHT AND SCREEN VARIES REFER TO PLAN)
N.T.S.



NOTES:
1. CONTRACTOR TO VERIFY DIMENSIONS ON SITE AND PROVIDE SHOP DRAWINGS FOR APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO FABRICATION
2. ALL POSTS AND RAILS SHALL BE SCHEDULE 40 GALVANIZED STEEL PIPE, ELECTROSTATICALLY PAINTED BLACK, AND CONFORMING TO CURRENT SPECIFICATIONS FOR BLACK AND HOT DIPPED ZINC COATED (GALVANIZED) WELDED AND SEAMLESS PIPE FOR ORDINARY USES.
3. ALL HARDWARE TO BE GALVANIZED.
4. ALL FENCE COMPONENTS TO BE OF A SUITABLE ALUMINUM ALLOY OR OF A STEEL DUCTILE IRON, ALSO PAINTED BLACK.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.
6. LINE POSTS SHALL BE SET AT 3.0m CENTRES
7. BOTTOM RAIL AND FINISHED GRADE 38-75mm CLEARANCE MAX.

3 / D-2 CHAIN LINK FENCE w/ SINGLE GATE (HEIGHT AND SCREEN VARIES REFER TO PLAN)
N.T.S.

CLIENT
AMERICAN IRON AND METAL

9100 BOUL HENRI-BOURASSA E, MONTREAL-EST, QC

COPYRIGHT
This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by IBI Group is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general conformance before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies

ISSUES

No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2022-03-25
2	REISSUED FOR SPA	2022-12-20
3	ISSUED FOR TENDER	2023-02-06

KEY PLAN



CONSULTANTS

NOT FOR CONSTRUCTION

SEAL

PRIME CONSULTANT

IBI GROUP
Suite 200 - 360 James Street North
Hamilton ON L8L 1H5 Canada
tel 905 546 1010 fax 905 546 1011
ibigroup.com

PROJECT
McADOOS LANE

1533 McADOOS LANE, KINGSTON, ON

PROJECT NO:
124600

DRAWN BY:	CHECKED BY:
T. KEMP	**T. O'BRIEN**
PROJECT MGR:	APPROVED BY:
T. TUCKER	**T. O'BRIEN**

SHEET TITLE
LANDSCAPE DETAILS

SHEET NUMBER
D-2

ISSUE
1

SCALE CHECK
1 in
10mm

File Location: T:\124600_1533McAdoo\N17.0_Production\7.03_Design\05_Landscape\Sheets\124600LP.dwg Last Saved: February 6, 2023, by taylor.kemp Plotted: Monday, February 6, 2023 2:42:18 PM by Taylor Kemp