AMENDMENT NO.: 3
TO THE TENDER DOCUMENTS
Defence Construction (1951) Limited

CLOSING DATE/TIME:	As indicated on the *Electronic Bidding System*
PROJECT NO.:	KN229976_86810
AMENDMENT DATE:	October 16, 2026
PROJECT TITLE:	Fort Frontenac Arc Flash Study Repair Kingston, Ontario

TO ALL TENDERERS:

THE PURPOSE OF THIS AMENDMENT IS TO GIVE EFFECT TO THE FOLLOWING:

1. Tenderers are advised that the Tender Closing date has been changed to **October 29, 2026.** The closing time and location remains unchanged.
2. Reference Section 01 11 00 Paragraph 1.16.5 and **INSERT:**
   " 1.16.5.1 Building FF03, FF04, FF08, and FF10 to require temporary services. Minor shutdown to remaining buildings may be required outside of operating hours, at the approval of the DCC Representative."
3. Tenderers are advised, for the purpose of bidding, assume five (5) knockout covers are required for each panel, where not indicated in the drawings.
4. Reference Drawing Sheet 521 Drawing Notes and **INSERT**:

   " 8. Assume 2ft x 4ft acoustic ceiling tile. For the purpose of bidding, assume no conduit replacements are required.
5. Reference Drawing Sheet 522 Drawing Notes and **INSERT**:

   " 5. Assume 2ft x 4ft acoustic ceiling tile. For the purpose of bidding, assume no conduit replacements are required.
6. Reference Drawing Sheet 531 Drawing Notes 8 and **ADD** "Assume #2 MI Cable. 40m Length for removal."
7. Reference Drawing Sheet 541 Drawing Notes and **INSERT**:

   " 6. Assume 2ft x 4ft acoustic tile ceiling . For the purpose of bidding, assume no conduit replacements are required.
8. Reference Drawing Sheet 550 Drawing Note #1 and **ADD** "Assume (1) One 15A 1P breaker for each panel."

9. Reference Drawing Sheet 582 Drawing Note #1 and **DELETE** “REPLACE MAIN FEEDER IF THE TEST DETERMINES DETERIORATION OR DEEMED UNSAFE. CARRY FOR REPLACEMENT OF MAIN FEEDER AS PROVISIONAL COST.” and **REPLACE** with “NOTIFY THE DCC REPRESENTATIVE OF THE MAIN FEEDER STATE OF DETERIORATION .”

End of Amendment No. 3